



**Resources
Regulator**

FWP0001933

PINE DALE MINE FORWARD PROGRAM

Wednesday 1 July 2026 to Saturday 30 June 2029



Summary

Detail	
Mine	Pine Dale Mine
Reference	FWP0001933
Forward program commencement date	Wednesday 1 July 2026
Forward program end date	Saturday 30 June 2029
Forward program revision (if applicable)	
Contact	Jarvis Lulham
Mining leases	ML 1569 (1992), ML 1578 (1992), ML 1637 (1992), ML 1664 (1992)
Project location	Enhance Place Pty Limited
Date of submission	Friday 18 September 2026
Document URL	https://www.energyaustralia.com.au/about-us/energy-generation/pine-dale-coal-mine/yarraboldy-stage-1
Security reminder: Please exercise caution before opening external links. If a link appears suspicious, avoid clicking it and report it to the Resources Regulator.	

Important

The department may make the information in your program and any supporting information available for inspection by members of the public, including by publication on its website or by displaying the information at any of its offices. If you consider any part of your program to be confidential, please communicate this to the department via the message function on this submission within the Resources Regulator Portal.

Three-year forecast - surface disturbance activities

Project description

Pine Dale Mine is located at Blackmans Flat approximately 16km north of Lithgow, on the Castlereagh Highway. The site is approximately 3km from the Mt. Piper Power Station and immediately across from the Springvale Joint Venture Coal Preparation and Handling Facility. Operations were approved under Project Approval PA 10_0041 by the Department for Planning and Infrastructure on 20/02/2011, permitting mining operations to be carried out until 31 December 2014. The approval allowed the extraction of up to 800,000t of ROM coal to be extracted from the Yarraboldy Extension at a maximum rate of 350,000 tpa. Pine Dale is operated by Enhance Place Pty Ltd (Enhance Place). Available coal within the approved mining area has since been exhausted and in April 2014 the site was placed under care and maintenance. It is expected the mine will remain in care and maintenance until planning approvals are obtained to allow mining to resume, or a decision is taken to permanently close the mine.

Description of surface disturbance activities

Exploration activities

Exploration activities are likely to be limited to desktop assessments based of known coal reserves in the Mining Leases to inform potential future mining activities. There are no exploration drilling activities proposed to be undertaken during the period of this forward program. Exploration activities are occurring as required under the Works Program for EL7621.

Construction activities

There are no planned construction activities to be undertaken during the period of this forward program while the site is in care and maintenance relating to buildings, mining equipment or other mining related infrastructure.

Mining schedule

Mining development method and sequencing and general mine features.

There are no approved coal reserves in the Mining Lease authorised for extraction at this time. No mining activity will therefore take place while the site is in care and maintenance during the forward program period. Exploration activities are occurring as required under the Works Program for EL7621.

Areas identified for emplacements, the sequencing of emplacements, construction, and management.

No planned rock or overburden emplacement works are expected to be undertaken during the forward program period.

Processing infrastructure activities and the location of tailings facilities and schedule for emplacement.

No planned coal processing activities are expected to take place during the forward program period. There is no active infrastructure or tailings facilities.

Waste disposal and materials handling operations.

Waste at Pine Dale will be disposed of appropriately in accordance with its waste type. Details on how waste will be disposed of at Pine Dale are summarised below. General Solid Waste (Putrescible) As there will be a minimal number of employees on site, there will be minimal putrescible waste generated. General waste bins will be available at the site office for collection. These bins will be collected and emptied as part of the maintenance program. Sewage Sewage management facilities will be maintained on site during the care and maintenance period and regular inspections and pump out will be undertaken as required. Hydrocarbons There are no hydrocarbons e.g.

fuel or oil, stored at the site currently or proposed to be at the site in this Forward Program period. Contaminated Soils There are no known contaminated soils occurring at Pine Dale. In the event that contaminated soil is identified, the material would either be treated in situ or disposed of offsite by a licenced contractor.

Key production milestones

MATERIAL	UNIT	YEAR 1	YEAR 2	YEAR 3
Stripped topsoil (if applicable)	(m ³)	0	0	0
Rock/overburden	(m ³)	0	0	0
Ore	(Mt)	0	0	0
Reject material¹	(Mt)	0	0	0
Product	(Mt)	0	0	0

¹This includes coarse rejects, tailings and any other wastes resulting from beneficiation.

Three-year rehabilitation forecast

Rehabilitation planning schedule

Rehabilitation planning schedule

Under Schedule 3, Condition 54 of the Project Approval, Pine Dale is required to progressively rehabilitate the site as soon as reasonably practicable. Enhance Place is investigating final land use options with relevant landowners and key stakeholders. This would be progressed over the three year forward program period. The outcome of these assessment and discussions with stakeholders will inform the rehabilitation schedule. Rehabilitation maintenance will occur on the established rehabilitated areas which will consist of tree planting, targeted topsoil application and weed management. If a decision is made for closure at Pine Dale, then the Annual Rehabilitation Report and Forward Program would be updated and rehabilitation completed to meet the requirements of Plan 1 and 2 – Final Landform and Rehabilitation Plan.

Stakeholder consultation

Consultation will be undertaken with the relevant stakeholders as required during the forward program period if the care and maintenance status of Pine Dale mine changes. Pine Dale is progressing with a partial mining lease relinquishment consultation with the relevant landowners will be undertaken to progress the relinquishment. The key stakeholders that will be consulted during the forward program period will include but not be limited to: • The NSW Resource Regulator; • Community Consultative Committee • Department of Planning Housing and Infrastructure • NSW EPA; • Lithgow City Council; • WaterNSW; • Department of Industry – Land and water Division (now DCCEEW); and • Forestry Corporation of NSW; • Private Landowners • Centinel Coal

Rehabilitation studies, risk assessments and/or design work

A risk assessment was completed as part of the preparation for the RMP. This assessment identified rehabilitation risks and current control measures in place. Risks associated with finalising rehabilitation at Pine Dale were considered low. Soil testing and analysis on top soil stockpile and rehabilitated areas. Annual flora surveys have been undertaken on previously rehabilitated areas, which provides data to measure rehabilitated areas against completion criteria. These surveys include: • Species richness; • Habitat features; • Flora surveys; • Ecosystem function analysis; • Species density; • Soil analysis ; and • Forest structure Results from these monitoring surveys are used to identify success and failures in the applied rehabilitation techniques. This highlights rehabilitation methods that will be successful for future rehabilitation. Rehabilitation methods will continue to be developed in accordance with best practice based on mine rehabilitation research and success achieved at other mine sites in the local area. Pine Dale will also continue monitoring and reporting through the Annual Rehabilitation Monitoring report. Actions and works recommended in this report will be implemented to ensure rehabilitation is progressing towards the targeted criteria.

Rehabilitation research and trials

RRT NUMBER	PROJECT/TRIAL NAME	OBJECTIVE OF TRIAL/PROJECT	METHODOLOGY	EXPECTED DATE OF COMPLETION	STATUS
---------------	--------------------	----------------------------	-------------	--------------------------------	--------

Rehabilitation maintenance and corrective actions

Maintenance and corrective actions will continue to ensure rehabilitation is undertaken by suitably qualified personnel in accordance with relevant guidelines. Rehabilitation monitoring and treatment will continue, including soil improvement, erosion control and weed management. Minor erosion has been identified in three areas of the site. Minor earthworks, hay bale placement and monitoring will be undertaken as required. Some potential erosion from stock crossing the creek was noted by the RR, and it was suggested this could be fenced off. This proposal has been challenged, on the basis the stock crossing is important to the landholder who needs the stock to be able to water at that position. Enhance agreed to discuss with the landholder and agree a workable method to address the erosion issue while also meeting landholder needs. This remains in progress. Supplementary tube stock planting is planned in sections of Area A to improve tree coverage within established rehabilitation areas. A review of the Area A drop structures found them to be suitable, with no evidence of erosion or performance issues. Established vegetation within the structures supports rehabilitation outcomes and unnecessary disturbance may be counterproductive. Ongoing monitoring will continue and maintenance undertaken if required. Maintenance activities, including fencing, weed control, feral animal management and minor drainage works, will continue.

Rehabilitation schedule

2027 Planned actions: - Apply to relinquish Eastern Area Rehabilitation. - Progress EL7621 work program to explore future mining. - Progress discussions with Lithgow Council on post-mining land use for waste facility. Comments: - Complete advanced rehabilitation to satisfy "progress as soon as reasonably practical". (Note: other areas not ready for rehabilitation due to possible future land uses). - Progress toward power station market opportunity in the post-2030 period (depending on other mining approval outcomes). - Future land use may require changes to final rehabilitation plans to improve future land use options over base plan. 2028 Planned actions: - Progress EL7621. - Progress future land use work with Council. Comments: As above. 2029 Planned actions: - Progress EL7621 work program. - Progress future land use work with Council. Comments: - Likely either approval work progressing, or decision to move to mine closure if other sources of coal for Mt Piper are approved by then. - Expect to have a clearer position on the future land use option by 2029, allowing it to be pursued further or discarded if not progressing.

Completion of rehabilitation

Active progression towards relinquishment is currently taking place on the Eastern area of the site. We are working towards the application for relinquishment during the Forward Program period. We have addressed landholder requests and subdivided the land ready for transfer of rehabilitated areas back to the landholder. We are in the process of engaging an advisor to assist with documentation requirements to prepare our relinquishment application. Should this process go to plan we would aim to apply for departmental approval in late 2026 or 2027. This should retract the leases back from the farming areas simplifying future landholder arrangements when the future of the site is finalised.

Subsidence remediation for underground operations

The site does not have a history of subsidence and there have been no recorded incidents during active mining operations. In the 2021 risk assessment completed for the RMP, the risk of subsidence was considered low.

Progressive mining and rehabilitation statistics

Three-yearly forecast cumulative disturbance and rehabilitation progression

Forecast		UNIT	YEAR 1	YEAR 2	YEAR 3
A1	Total disturbance footprint - surface disturbance	(ha)	84.02	84.02	84.02
B	Total active disturbance	(ha)	41.77	41.77	41.77
P	Total new area of land proposed for active rehabilitation	(ha)	0	0	0

Rehabilitation key performance indicators (KPIs)

Forecast		UNIT	YEAR 1	YEAR 2	YEAR 3
O	Total new disturbance area during reporting period	(ha)			
P	Total new area of land proposed for rehabilitation during the reporting period	(ha)			
Q	Annual rehabilitation to disturbance ratio				

Attachment 1 - Reporting Definitions

REPORTING CATEGORY		DEFINITION
A	Total disturbance footprint - surface disturbance	All areas within a mining lease that either have at some point in time or continue to pose a rehabilitation liability due to surface disturbance activities. The total disturbance footprint is the sum of the total active disturbance, decommissioning, landform establishment, growth medium development, ecosystem and land use establishment, ecosystem and land use development and rehabilitation completion (see definitions below). Underground mining operations should not include the footprint of underground mining areas/subsidence management areas in the total disturbance footprint.
B	Total active disturbance	Includes on-lease exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste rock emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped) and temporary stabilised areas (e.g. areas sown with temporary cover crops for dust mitigation and temporary rehabilitation).
C	Rehabilitation - land preparation	Includes the sum of all disturbed land within a mining lease that have commenced

REPORTING CATEGORY	DEFINITION
	any, or all, of the following phases of rehabilitation - decommissioning, landform establishment and growth medium development. Refer to the glossary of terms in this document for the definition of these phases of rehabilitation.
D	Ecosystem and land use establishment Includes the area which has been seeded/planted with the target vegetation species for the intended final land use. However, vegetation has not matured to a stage where it can be demonstrated that it will be sustainable for the long term and or require only a maintenance regime consistent with target reference/analogue sites. Typically, rehabilitation areas would be in this phase for at least two years (and usually more) before rehabilitation can be classified as being in the ecosystem and land use development phase. This phase does not apply to infrastructure areas that are being retained as part of final land use for the site.
O	N/A The area of any new active disturbance that will be created during the next three years, as defined under definition A1 (definition A1 Table 5).
P	N/A The sum of any new rehabilitation to be commenced in the next three years. These areas may be in the phases "Rehabilitation - Land Preparation" or the "Ecosystem & Land Use Establishment" (definitions C & D in Table 5).

REPORTING CATEGORY		DEFINITION
Q	N/A	The rehabilitation to disturbance ratio (P:O) indicates how many hectares of new rehabilitation are undertaken for each hectare of land disturbed during the three years. A ratio of 1:1 indicates that the area of new rehabilitation and disturbance in that period are the same.

Attachment 2 - Definitions

WORD	DEFINITION
Active	In the context of rehabilitation, land associated with mining domains is considered 'active' for the period following disturbance until the commencement of rehabilitation.
Active mining phase of rehabilitation	In the context of rehabilitation, the active mining phase of rehabilitation constitutes the rehabilitation activities undertaken during mining operations such as salvaging and managing soil resources, salvaging habitat resources, and native seed collection. This phase also includes management actions taken during operations to manage risks to rehabilitation and enhance rehabilitation outcomes such as selective handling of waste rock and management of tailings emplacements.
Analogue site	In the context of rehabilitation, an analogue site is a 'reference site' that represents an example of the defining characteristics (such as vegetation composition and structure or agricultural productivity) of the final land use. Characteristics of analogue sites can be assessed to develop the rehabilitation objectives and completion criteria for final land use domains.
Annual rehabilitation report and forward program	As described in the Mining Regulation 2016.
Annual reporting period	As defined in the Mining Regulation 2016.

WORD	DEFINITION
Closure	A whole-of-mine-life process, which typically culminates in the relinquishment of the mining lease. It includes decommissioning and rehabilitation to achieve the approved final land use(s).
Decommissioning	The process of removing mining infrastructure and removing contaminants and hazardous materials.
Decommissioning Phase of Rehabilitation	Activities associated with the removal of mining infrastructure and removal and/or remediation of contaminants and hazardous materials. In the context of the rehabilitation management plan this phase of rehabilitation may also include studies and assessments associated with decommissioning and demolition of infrastructure or works carried out to make safe or 'fit for purpose ' built infrastructure to be retained for future use(s) following lease relinquishment.
Department	Department of Primary Industries and Regional Development.
Disturbance	See Surface Disturbance.
Disturbance area	An area that has been disturbed and that requires rehabilitation. This may include areas such as on-licence exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped), and areas requiring rehabilitation that are temporarily stabilised (i.e. managed to minimise dust generation and/or erosion).

WORD	DEFINITION
Domain	An area (or areas) of the land that has been disturbed by mining and has a specific operational use (mining domain) or specific final land use (final land use domain). Land within a domain typically has similar geochemical and/or geophysical characteristics and therefore requires specific rehabilitation activities to achieve the associated final land use.
Ecosystem and Land Use Development	This phase of rehabilitation consists of the activities to manage maturing rehabilitation areas on a trajectory to achieving the approved rehabilitation objectives and completion criteria. For vegetated land uses this phase may include processes to develop characteristics of functional self-sustaining ecosystems, such as nutrient recycling, vegetation flowering and reproduction, and increasing habitat complexity, and development of a productive, self-sustaining soil profile. This phase of rehabilitation may include specific vegetation management strategies and maintenance such as tree thinning, supplementary plantings and weed management.
Ecosystem and Land Use Establishment	This phase of rehabilitation consists of the processes to establish the approved final land use following construction of the final landform. For vegetated land uses this rehabilitation phase includes establishing the desired vegetation community and implementing land management activities such as weed control. This phase of rehabilitation may also include habitat augmentation such as installation of nest boxes.
Exploration	Has the same meaning as that term under the State Environmental Planning Policy (Mining,

WORD	DEFINITION
	Petroleum Production and Extractive Industries) 2007.
Final landform and rehabilitation plan	As defined in the Mining Regulation 2016.
Final land use	As defined in the Mining Regulation 2016.
Form and way	Means the form and way approved by the Secretary. Approved form and way documents are available on the department's website.
Growth Medium Development	This phase of rehabilitation consists of activities required to establish the physical, chemical and biological components of the substrate required to establish the desired vegetation community (including short lived pioneer species. This phase may include spreading the prepared landform with topsoil and/or subsoil and/or soil substitutes, applying soil ameliorants to enhance the physical, chemical and biological characteristics of the growth media, and actions to minimise loss of growth media due to erosion.
Habitat	Has the same meaning as that term under the Biodiversity Conservation Act 2016 and the Fisheries Management Act 1994 (as relevant).
Indicator	An attribute of the biophysical environment (e.g. pH, topsoil depth, biomass) that can be used to approximate the progression of a biophysical process. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion

WORD	DEFINITION
	criterion (i.e. defined end point). It may be aligned to an established protocol and used to evaluate changes in a system.
Land	As defined in the Mining Act 1992.
Landform Establishment	This phase of rehabilitation consists of the processes and activities required to construct the final landform. In addition to profiling the surface of rehabilitation areas to the approved final landform profile this phase may include works to construct surface water drainage features, encapsulate problematic materials such as tailings, and prepare a substrate with the desired physical and chemical characteristics (e.g. rock raking or ameliorating sodic materials).
Large mine	As defined in the Mining Regulation 2016.
Lease holder	The holder of a mining lease.
Life of mine	The timeframe of how long a mine is approved to mine, from commencement to closure.
Mine rehabilitation portal	Means the Resources Regulator's online portal that lease holders must use (via a registered account) to:

WORD	DEFINITION
	• upload rehabilitation geographical information system (GIS) spatial data • develop rehabilitation GIS spatial data (using online tracing functions) • generate rehabilitation plans and rehabilitation statistics using the map viewer and Rehabilitation Key Performance Indicator functionalities. Data submitted to the mine rehabilitation portal is collated in a centralised geodatabase for use by the Resources Regulator to regulate rehabilitation performance of lease holders.
Mining area	As defined in the Mining Act 1992.
Mining domain	A land management unit with a discrete operational function (e.g. overburden emplacement), and therefore similar geophysical characteristics, that will require specific rehabilitation treatments to achieve the final land use(s).
Mining land	As defined in the Mining Act 1992.
Native vegetation	Has the same meaning as that term under section 60B of the Local Land Services Act 2013.
Overburden	Material overlying coal or a mineral deposit.
Performance indicator	An attribute of the biophysical environment (for example pH, slope, topsoil depth, biomass) that can be used to demonstrate achievement of a rehabilitation objective. It can be measured and audited to

WORD	DEFINITION
	demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion, that is, a defined end point. It may be aligned to an established protocol and used to evaluate changes in a system.
Phases of rehabilitation	The stages and sequences of actions required to rehabilitate disturbed land to achieve the final land use. The phases of rehabilitation are: • active mining • decommissioning • landform Establishment • growth medium development • landform Establishment • ecosystem and land use establishment • ecosystem and land use development
Progressive rehabilitation	The progress of rehabilitation towards achieving the approved rehabilitation completion criteria. This may be described in terms of domains, phases, performance indicators and rehabilitation completion criteria.
Rehabilitation Completion	The final phase of rehabilitation when a rehabilitation area has achieved the approved rehabilitation objectives and rehabilitation completion criteria for the final land use. Rehabilitation areas may be classified as complete when the Resources Regulator has determined in writing that the relevant

WORD	DEFINITION
	rehabilitation obligations have been fulfilled following submission of <i>Form ESF2 Rehabilitation completion and/or review of rehabilitation cost estimate application</i> by the lease holder.
Rehabilitation Completion criteria	As defined in the Mining Regulation 2016.
Rehabilitation cost estimate	As defined in the Mining Regulation 2016.
Rehabilitation management plan	As defined in the Mining Regulation 2016.
Rehabilitation objectives	As defined in the Mining Regulation 2016.
Rehabilitation risk assessment	As defined in the Mining Regulation 2016.
Rehabilitation schedule	The defined timeframes for progressive rehabilitation set out in the forward program.
Relevant stakeholders	Means any persons or bodies who may be affected by the mining operations, including rehabilitation, carried out on the lease land, and includes: • the relevant development consent authority • the local council • the relevant landholder(s) • community consultative committee (if required under the development consent) or equivalent

WORD	DEFINITION
	consultative group • affected land holder(s) • government agencies relevant to the final land use • affected infrastructure authorities (electricity, telecommunications, water, pipeline, road, rail authorities) • local Aboriginal communities, and • any other person or body determined by the Minister to be a relevant stakeholder in relation to a mining lease.
Risk	The effect of uncertainty on objectives. It is measured in terms of consequences and likelihood (AS/NZS ISO 31000:2009).
Secretary	The Secretary of the department.
Security deposit	An amount that a mining lease holder is required to provide and maintain under a mining lease condition, to secure funding for the fulfilment of obligations under the lease (including obligations that may arise in the future).
Surface disturbance	Includes activities that disturb the surface of the mining area, including mining operations, ancillary mining activities and exploration.

WORD	DEFINITION
Tailings	A combination of the fine-grained solid material remaining after the recoverable metals and minerals have been extracted from the mined ore, and any process water ² .
Waste	Has the same meaning as that term under the <i>Protection of the Environment Operations Act 1997</i> .

²Commonwealth of Australia (DITR), 2007. Tailings Management.

Attachment 3 - Plans

Pine Dale Mine 3 year forecast data.pdf

Pine Dale Mine 3 year forecast data.pdf

Pine Dale Mine 3 year forecast data.pdf